

Application No.: A.24-12-XXX
Exhibit No.: _____
Witness: Brian Walker

**PREPARED DIRECT TESTIMONY OF
BRIAN WALKER
ON BEHALF OF
SOUTHERN CALIFORNIA GAS COMPANY
(CHAPTER 4 - ENGINEERING DESIGN)**

**BEFORE THE PUBLIC UTILITIES COMMISSION
OF THE STATE OF CALIFORNIA**

December 20, 2024

TABLE OF CONTENTS

I.	INTRODUCTION	1
II.	BACKGROUND INFORMATION	2
	A. Overview.....	2
	B. Engineering Design Project Management Overview.....	3
	C. Project Lifecycle.....	4
III.	DESCRIPTION OF PHASE 2 PRE-FEED AND FEED ACTIVITIES	6
	A. Engineering Design & Project Management Activities.....	6
	1. Description of Phase 2 Scope and Activities	6
	B. Environmental Activities and Land & Right-of-Way.....	10
	C. Description of Pipeline System Components to Be Evaluated During Phase 2	11
IV.	SOCALGAS SYSTEM DESIGN.....	13
	A. Project Team Activities.....	13
	1. Project Management	14
	2. Engineering.....	15
	3. Engineering Design Project Controls.....	15
	4. Cost and Schedule Controls	15
	5. Cost Estimating.....	16
	6. Construction Management	16
	7. Operations	16
	8. Ministerial Permitting and Environmental Support.....	17
	9. Public Outreach.....	17
	B. Procurement	18
	C. Schedule.....	19
V.	COST FORECAST.....	20
	A. Phase 2 Cost Forecasting Methodology.....	20
	B. Cost Controls	22
VI.	CONCLUSION.....	23
VII.	CHAPTER 4 GLOSSARY	24
VIII.	QUALIFICATIONS	29

**PREPARED DIRECT TESTIMONY OF
BRIAN WALKER
(ENGINEERING DESIGN)**

I. INTRODUCTION

My name is Brian Walker, and I am the Director of Project Management at Southern California Gas Company (SoCalGas or Company). My testimony supports the Application for Authorization to Implement Revenue Requirement for Costs to Enable Commencement of Phase 2 Activities for Angeles Link (Application). The purpose of my testimony is to present the forecasted costs of Angeles Link Phase 2 (Phase 2) activities necessary to support identification of a preferred system route, perform engineering design, environmental assessments, and project management activities associated with progressing the Angeles Link clean renewable hydrogen pipeline system through Front-End Engineering Design (FEED). The Phase 2 engineering design scope of work builds on information developed in the Phase 1 feasibility studies. Phase 2 will result in engineering design being advanced to define the scope and technical requirements of the Angeles Link system as well as the production of a Class 3¹ cost estimate for the Angeles Link system, a detailed project schedule, and certain permitting information.

SoCalGas currently estimates that Angeles Link Phase 2 activities will have a total duration of approximately 30 months following a decision in this proceeding, with an estimated overall cost of approximately \$266 million (inclusive of those costs identified in the Testimony of Amy Kitson). The subset of costs presented in this testimony for advancing engineering and performing project management activities for the Angeles Link system through the FEED study total approximately \$216 million. These costs are inclusive of a limited set of contracting-related activities that will commence in 2025. These limited activities will allow SoCalGas to retain vendors promptly after a decision is issued in this proceeding to conduct critical-path work to support meeting the timing goals discussed in the Testimony of Neil Navin. All activities and

¹ Estimating classes are described in AACE International (AACEi), *Recommended Practice No. 97R-18 Cost Estimate Classification System - As Applied in Engineering, Procurement, and Construction for the Pipeline Transportation Infrastructure Industries* (AACEi RP 97R-18) (August 7, 2020) at 5, available at: <https://web.aacei.org/docs/default-source/rps/97R-18.pdf>; also see, Section V.A. below for more information on SoCalGas's Phase 2 estimating approach.

1 costs presented in my testimony are based on the current description of Angeles Link, as
2 depicted by Mr. Navin.

3 **II. BACKGROUND INFORMATION**

4 **A. Overview**

5 SoCalGas proposes to develop a hydrogen pipeline system to transport clean renewable
6 hydrogen from regional third-party producers to demand in Central and Southern California,
7 including the Los Angeles Basin. In Decision (D.) 22-12-055 (Phase 1 Decision), the
8 Commission authorized SoCalGas to establish the Angeles Link Memorandum Account
9 (ALMA) to track costs related to conducting certain activities, including the Phase 1 feasibility
10 studies. The findings of those feasibility studies are described by Mr. Navin. Feasibility studies,
11 which broadly analyze various aspects of project development, provide a foundation from which
12 a project can be further developed.

13 The proposed Phase 2 activities described below, which consist of identifying a preferred
14 system route, conducting refined engineering design, and environmental assessments, will build
15 upon the Phase 1 feasibility studies. For example, feasibility-level Phase 1 engineering design-
16 related studies including, but not limited to, the Preliminary Routing Configuration Analysis,
17 Pipeline Sizing and Design Criteria, and Evaluation of Applicable Safety Requirements, provide
18 technical considerations that will be leveraged in Phase 2.²

19 Engineering design activities for Angeles Link Phase 2 activities will identify a preferred
20 system route, advance engineering to the 30% engineering design level and develop project
21 execution plans. The work will utilize the Angeles Link scope and definition described by Mr.
22 Navin, subject to further refinement in Phase 2.³ Further, environmental, land and right-of-way
23 and stakeholder engagement⁴ activities will be completed during Phase 2 to collect pertinent
24 data. This data will inform the engineering design and planning activities. Collectively, the
25 design drawings, documents and reports that will be created are the deliverables for FEED.

² See Testimony of Neil Navin for a detailed summary of the Phase 1 studies.

³ The scope of work is based on the four preliminary preferred routes identified at the conclusion of Phase 1, which ranged between 390 miles to 481 miles and were anticipated to require two or three compressor stations.

⁴ See Testimony of Amy Kitson for a summary of stakeholder engagement activities.

1 Phase 2 activities are expected to generate the deliverables and information necessary to advance
2 the Angeles Link concept to a defined proposed project scope and generate system design data in
3 support of a potential future Certificate of Public Convenience and Necessity (CPCN)
4 application and other long-lead permit applications.

5 The engineering design activities described in my testimony will be completed in
6 collaboration with the project development and programmatic activities described by Ms. Kitson.

7 **B. Engineering Design Project Management Overview**

8 SoCalGas will utilize its project delivery framework for infrastructure project
9 management and execution to conduct the Phase 2 activities described herein. The infrastructure
10 project planning process through which these activities are conducted is known as the Project
11 Delivery Model (also known as the stage-gate process).⁵ The Project Delivery Model process
12 encompasses key components required for planning, managing, controlling and executing
13 pipeline and complex facility infrastructure projects. Because it relies on project management
14 principles that are independent of the type of infrastructure project being designed and
15 implemented, the Project Delivery Model process is broadly applicable to a diverse range of
16 pipeline and facilities projects, including a clean renewable hydrogen system such as Angeles
17 Link. The development and execution of natural gas transmission pipeline projects are a
18 reasonable analog to a hydrogen transmission pipeline project such as Angeles Link.⁶ The
19 Project Delivery Model process has been developed and refined over the last 10+ years to
20 incorporate lessons learned and best practices to improve project delivery performance for
21 SoCalGas pipeline, valve, and compressor station projects and is well suited to the Phase 2
22 activities described herein. SoCalGas has the skilled workforce, resources, processes, controls,

⁵ The Project Delivery Model was initially pioneered for SoCalGas's Pipeline Safety Enhancement Plan (PSEP). SoCalGas's application of this process, as well as broader oversight and controls, dates to the earliest PSEP projects and has been found reasonable by the Commission in numerous instances. *See* D.16-12-063 at 59 (COL 15), D.19-02-004 at 10-11, 97-99 (FOF 13, 19, and 33), and D.19-03-025 at 44. Although initially developed for PSEP, SoCalGas now employs the stage-gate methodology company-wide for large projects, as well as a scalable stage-gate methodology for smaller, standard design projects.

⁶ The Angeles Link Phase 1 Pipeline Sizing & Design Criteria (Design Study) identified: "A hydrogen gas pipeline system would have a similar architecture to a natural gas pipeline system, whereby similar facilities and pipeline system operation parameters would be employed." Design Study at 7.

1 and experience to manage the Phase 2 activities for Angeles Link (see additional discussion
2 below).

3 **C. Project Lifecycle**

4 The design and development of a pipeline system project is typically divided into a
5 number of stages. Corresponding to the advancement of project stages, a pipeline system's
6 engineering design is advanced through design cycles, which incrementally refine the technical
7 project details and support the development of cost estimates.⁷ The level of engineering detail is
8 expressed in percentage (%) of complete definition, which can range from 0% to 100%.

9 Dividing the project into stages also facilitates management and control of resources at different
10 levels throughout the project lifecycle. The figure (below) depicts a project lifecycle divided into
11 stages, which advance from the identification of a project to placing a project into operation.⁸

12 Phase 2 will consist of the Option Selection / Pre-FEED stage and the FEED stage.

13 In the first stage, referred to as the identification stage, the project idea is explored and
14 evaluated. In the second stage, referred to as the feasibility stage, feasibility studies are typically
15 conducted to provide an early assessment of a potential project's viability. Typically, at the
16 conclusion of the feasibility stage, the maturity level of project definition is between 0 to 2% and
17 results in a Class 5 cost estimate (-50%/+100% expected accuracy). With respect to Angeles
18 Link, as described by Mr. Navin, over the last two years SoCalGas has conducted preliminary
19 engineering and environmental feasibility studies to evaluate a variety of topics, including
20 production, demand end uses, pipeline configurations and storage solutions, and early project

⁷ SoCalGas follows the industry recommended practices developed by the Association for the Advancement of Cost Engineering International (AACEi) to benchmark the maturity level of project definition deliverables and the class of estimate associated with each stage of a project. The AACEi standards (*AACE RP 97R-18 Cost Estimate Classification System – As Applied in Engineering, Procurement, and Construction for the Pipeline Transportation Infrastructure* and *AACE RP 18R-97 Cost Estimate Classification System – As Applied in Engineering, Procurement, and Construction for the Process Industries*) indicate that as the project's deliverables are increased in quantity and progressively defined, the expected accuracy of the project estimate accuracy improves. However, even though projects of similar nature can be expected to fall within common accuracy ranges there can be outliers where the high range can be two to three times higher. Therefore, SoCalGas utilizes project risk reviews to assess specific project risks when establishing project schedules and estimates.

⁸ The project lifecycle depiction does not identify regulatory approvals, permitting, etc.


1 alternatives (collectively referred to as the Phase 1 studies). SoCalGas now proposes progressing
2 planning in Phase 2, including the selection of a preferred system route and FEED work.

3 Following the feasibility stage, the next stage is the option selection and Pre-FEED stage
4 during which the proposed project scope will be selected and refined. In this stage, an option
5 selection analysis is completed that will narrow the focus to a proposed project for progressive
6 engineering design activities in Pre-FEED. Certain activities supportive of selecting a preferred
7 system route are described by Ms. Kitson. Pre-FEED will typically produce a design of the
8 proposed project that substantially establishes the project's fundamental design concept and will
9 result in a maturity level of project definition between 1% to 15% and a Class 4 cost estimate (-
10 30%/+50% expected accuracy). Pre-FEED activities typically include the development of
11 technical details (specifications), preliminary calculations (e.g., hydraulics), route refinement,
12 site selection(s), planning, and early designs in preparation for FEED. The deliverables created
13 during Pre-FEED will be refined in the next stage, which is the FEED study stage.

14 In the FEED study stage activities will be completed to advance the project definition.
15 The proposed project definition will be advanced such that there are sufficient project
16 engineering, project data and completed technical studies to be able to develop applications to
17 seek regulatory approvals and permits, such as a CPCN. The maturity level of project definition
18 for the FEED study stage will typically land between 10% to 40% and result in a Class 3 cost
19 estimate (-20%/+30% expected accuracy). At this design level, the project scope is defined,
20 major equipment is selected, and a detailed list of project materials can be created. The
21 engineering details and planning activities produced in FEED provide a basis for the project
22 execution plan, which outlines how the project will be carried out. This stage also includes
23 development of detailed project cost estimates and schedules for the remaining duration of the
24 project.

25 After the FEED stage, a project will move into the execution phase, where permit
26 applications are submitted and processed, detailed engineering design is completed, and project
27 materials are procured, with construction subsequently occurring. Commensurate with the
28 advancement of detailed design, project cost estimates can be produced with increased accuracy.

1 Upon completion of construction, the project is tested to verify that it operates as designed and is
2 placed into service (i.e., commissioning), after which it is operated and maintained.⁹



4
5 **Figure 1. Typical project lifecycle stages**

6 **III. DESCRIPTION OF PHASE 2 PRE-FEED AND FEED ACTIVITIES**

7 **A. Engineering Design & Project Management Activities**

8 **1. Description of Phase 2 Scope and Activities**

9 The costs identified in this testimony are necessary to conduct timely procurement of
10 services, support the identification of a preferred system route, complete Pre-FEED activities,
11 perform environmental studies, perform land and right-of-way (ROW) studies, and complete
12 FEED which will inform the development of a Class 3¹⁰ cost estimate for Angeles Link. Phase 2
13 activities are incremental to and will build upon the findings from Phase 1 feasibility-level
14 activities.

15 SoCalGas intends to conduct certain contracting activities for vendor services, such as
16 primary engineering design and environmental services, necessary to conduct Phase 2 activities
17 discussed in my testimony and by Ms. Kitson. To maintain the proposed 30-month Phase 2
18 schedule, the selection of these primary contractor services needs to occur prior to starting the
19 option selection and Pre-FEED activities. The selection of these vendors requires a series of
20 activities to occur which will include the advancement of contracting strategy, assessment of

⁹ Project Execution and Operate stage activities are not included in Phase 2 but are described herein to provide information and context about the entire project development lifecycle.

¹⁰ "Class 3 estimates are typically prepared to support full project funding requests and become the first of the project phase control estimates against which all actual costs and resources will be monitored for variations to the budget." AACEi RP 97R-18 at 10.

1 potential service providers, development of contract technical exhibits and the execution of a
2 Request for Proposal (RFP) process which will culminate with the selection of vendors.¹¹ These
3 activities support the selection of skilled service providers at competitive rates and support the
4 proposed 30-month Phase 2 schedule shown in Figure 3 below.

5 **a. Option Selection and Pre-FEED Activities**

6 At the beginning of Phase 2, a system route options analysis will be performed that will
7 further consider the potential Angeles Link routes and route variation identified in Phase 1 and
8 ultimately select a preferred system route for further development. The activities that will be
9 conducted in support of the system route options analysis are described by Ms. Kitson. This
10 system route options analysis will be closely coordinated with, and receive inputs from, activities
11 described in this testimony. These alternatives will be shared with stakeholders to obtain input
12 for SoCalGas to consider as part of its preferred route selection (*see* Section IV.A., Public
13 Outreach, below). Once a preferred system route is identified, SoCalGas will advance
14 development of the preferred system route, including engineering design and planning, to
15 develop the information needed to complete Pre-FEED for the preferred system route.

16 SoCalGas will also commence the Pre-FEED stage of engineering design at the
17 beginning of Phase 2. Preliminary engineering design development for both the potential
18 pipeline and compressor stations will occur during this stage, which will result in a conceptual
19 design of the Angeles Link system. During this stage, documentation such as specifications,
20 technical documents and initial designs will be developed, which are foundational to the
21 development of a proposed project. Project planning deliverables will also be created to
22 document project execution, control and communication plans. These documents will guide
23 activities and set expectations for deliverables in future stages of the project. This
24 documentation will mature the project definition and support completion of a FEED study.

25 Activities expected to occur during the Pre-FEED stage of Phase 2 are:

- 26 • Ramp-up of project team resources;
- 27 • Mobilize engineering services vendor(s);
- 28 • Advance design development requirements (Basis of Design);

¹¹ Further information on the procurement of services can be found in Section IV.B, Procurement, of this testimony.

- 1 • Select a preferred system route;
- 2 • Develop preliminary proposed pipeline routing and engineering design;
- 3 • Develop preliminary proposed compressor station siting and engineering design;
- 4 • Collect project data and information (execute surveys and studies);
- 5 • Refine identification of permitting requirements for the preferred system route;
- 6 • Prepare preliminary proposed project schedule (Level 2);
- 7 • Prepare Class 4 cost estimate;
- 8 • Develop project quality plan;
- 9 • Refine estimate of project resources and schedule for FEED study stage;
- 10 • Develop and execute project communication plan (e.g., project coordination
- 11 meetings);
- 12 • Perform preliminary project risk review;
- 13 • Refine preliminary environmental and safety assessment of the preferred system
- 14 route;
- 15 • Perform necessary design reviews; and
- 16 • Prepare Pre-FEED report(s) for the Angeles Link system.

17 **b. FEED**

18 The FEED stage of Phase 2 will take the preliminary designs and technical specifications
19 identified during Pre-FEED and further advance and refine these details into plans and design
20 drawings that describe the proposed infrastructure. The objective of FEED will be to develop an
21 engineering design that is at approximately 30% definition, execute studies to select major
22 equipment, execute studies to identify and mitigate technical and operational issues, increase the
23 accuracy of the proposed project cost estimate, develop the project execution plan, and perform
24 value engineering on the proposed project.¹²

25 Activities expected to occur during the FEED stage of Phase 2 are:

- 26 • Ramp up project team resources;

¹² A value engineering study is a systematic approach used to improve the value of the project by performing analysis, reviews and evaluations of the proposed project FEED design. Value engineering will seek to optimize the balance between performance, quality, safety and cost of the proposed project. As appropriate, the FEED study is refined to reflect improvements identified in the value engineering process.

- 1 • Mobilize additional engineering services vendor(s) resources;
- 2 • Refine design development requirements (Basis of Design);
- 3 • Perform FEED deliverable assessment;
- 4 • Collect project data and information, including on topics such as:
 - 5 ○ Documenting existing site conditions;
 - 6 ○ Performing engineering surveys;
 - 7 ○ Regulatory;
 - 8 ○ Engineering and operational codes and standards;
 - 9 ○ Safety;
 - 10 ○ Environmental;
 - 11 ○ Land & ROW;
- 12 • Generate technical deliverables/studies, including but not limited to:
 - 13 ○ Major equipment;
 - 14 ○ Process diagrams;
 - 15 ○ Piping configurations;
 - 16 ○ Compressor plant configuration;
 - 17 ○ Hazard Identification (HAZID);
 - 18 ○ Material Data Sheets (MDS);
 - 19 ○ Long lead items (procurement);
- 20 • Prepare FEED drawings and schematics, including:
 - 21 ○ Refine and advance proposed pipeline routing and engineering design;
 - 22 ○ Refine and advance compressor station siting and engineering design;
- 23 • Quality management of the FEED study;
- 24 • Prepare contracting strategy (for execution stage);
- 25 • Prepare Land & ROW acquisition strategy;
- 26 • Prepare project schedule (Level 3);
- 27 • Estimate project cost (Class 3 cost estimate);
- 28 • Prepare Project Execution Plan;
- 29 • Prepare Operating Philosophy document;
- 30 • Perform communication coordination activities (e.g., project coordination
- 31 meetings);

- 1 • Prepare Project Risk Register;
- 2 • Perform Hazard and Operability Study (HAZOP) to identify potential hazards and
- 3 operability problems;
- 4 • Develop project specifications (detailed design, construction, etc.);
- 5 • Perform Value Engineering; and
- 6 • Prepare FEED study report for the Angeles Link system.

7 As noted above, preparing a more refined, i.e., Class 3, cost estimate is one objective of
8 the FEED stage. The project definition maturity level, which is dependent on the status of
9 technical and planning deliverables, drives the project's estimate class. The maturity level of the
10 project definition typically correlates with the percent of engineering design that has been
11 completed. As project definition is progressed in maturity level, the associated cost estimate
12 accuracy typically improves.¹³ AACEi has defined estimate accuracy ranges for typical pipeline
13 and process industry projects. At the conclusion of Phase 1, the Angeles Link system is at
14 approximately 1-2% project definition maturity level, which can produce Class 5 cost estimates
15 that can range in accuracy from -50% to +100%.¹⁴ Progressing to a Class 3 estimate in Phase 2
16 will facilitate the production of estimates with an expected accuracy of -20% to +30%.

17 After the FEED technical deliverables are completed, a refined view of the next stage of
18 work will be developed and, as a result, a more detailed project execution stage schedule and
19 cost estimate will be created. At the conclusion of the FEED stage, the completeness of FEED
20 documentation will be reviewed. The deliverables developed during the FEED stage are
21 intended to provide adequate information for regulatory and environmental project permitting.

22 **B. Environmental Activities and Land & Right-of-Way**

23 Environmental support from internal resources and third-party contractors will be utilized
24 to aid Angeles Link system routing, siting, and planning activities. Data gathered during the
25 Phase 1 desktop analysis will be leveraged to conduct further review of the preliminary preferred

¹³ In addition to the degree of maturity of the project definition, the range of accuracy for any particular estimate is also driven by other systemic risks such as level of familiarity with technology, unique/remote nature of project locations and conditions, complexity of the project and its execution, and other factors. AACEi RP 18R-97 at 4.

¹⁴ Class 5 estimates for various scenarios of Angeles Link reflecting a range of pipeline miles, pipe sizes, and numbers of compressor stations are presented within the Design Study at 63-64.

1 routes and refine potential environmental constraints identified in the Phase 1 studies. The team
2 will develop a portfolio of detailed assessments, including biological, cultural resources and site
3 assessment field work, which will inform the project’s schedule, estimating activities, and
4 permitting activities. Other Phase 2 environmental activities will also be conducted to support
5 FEED. The scope of these studies and activities will be guided by the Commission’s
6 Proponent’s Environmental Assessment¹⁵ checklist as well as other agency guidance (e.g.,
7 United States Fish & Wildlife Service, California Department of Fish & Wildlife, Native
8 American Heritage Commission). These studies will help to inform the development of the
9 engineering deliverables and overall proposed schedule and costs to complete the project and
10 incorporate into the Class 3 estimate.

11 Land and Right-of-Way activities during the Pre-FEED and FEED component of Phase 2
12 include non-labor costs associated with pre-acquisition due diligence activities related to
13 identification of the preferred route. The specific deliverables associated with Land and ROW
14 incorporate the development of a preliminary land acquisition plan, refining ownership and
15 existing ROW analyses conducted in Phase 1, a detailed title review of private parcels with
16 temporary and permanent easement acquisition needs identified through engineering and design,
17 preliminary land value market analysis, development of a land acquisition cost estimate, and
18 acquiring private owner consents to facilitate necessary survey activities.

19 C. Description of Pipeline System Components to Be Evaluated During Phase 2

20 A pipeline system like Angeles Link consists of many interconnected components that
21 are designed to safely work together. During Pre-FEED and FEED, these various components
22 will be evaluated holistically to define a system route and develop the engineering design of the
23 route and associated facilities. To forecast the cost of Phase 2 activities, a detailed list of
24 pipeline and compressor station-related deliverables was created, inclusive of pipeline system
25 components that are reasonably expected to be included in the Angeles Link system design. This
26 list leveraged information from the Phase 1 feasibility-level Pipeline Sizing & Design Criteria

¹⁵ A Proponent’s Environmental Assessment must be included with any application for authority to undertake a project that is not statutorily or categorically exempt from the requirements of the California Environmental Quality Act (CEQA). CPUC Rules of Practice and Procedure, available at: <https://www.cpuc.ca.gov/-/media/cpuc-website/divisions/administrative-law-judge-division/documents/rules-of-practice-and-procedure-may-2021.pdf>.

1 (Design Study). The following is a list of the components that may be part of the Angeles Link
2 system and will be addressed during the Pre-FEED and FEED study engineering design;
3 additional features may be necessary on a case-by-case basis:

- 4 • **Pipelines:** Tubular sections made from materials compatible with hydrogen to
5 transport the gas from one point to another. They must be designed to resist hydrogen
6 embrittlement and withstand the specific pressures and temperatures of hydrogen gas.
 - 7 1. **Compressors:** Mechanical equipment, typically found in transmission
8 stations, used to increase the pressure of hydrogen gas to adequate levels
9 for transmission through the pipeline. They are essential for maintaining
10 flow and overcoming frictional losses along the pipeline length.
 - 11 2. **Air Cooled Heat Exchangers:** Heat transfer equipment, typically found
12 in transmission stations, used to cool the hot discharge gas from
13 compressors to acceptable temperatures conducive to pipeline
14 transportation.
 - 15 3. **Valves:** Including isolation valves, control valves, and safety valves; these
16 components regulate, direct, or control the flow of hydrogen by opening,
17 closing, or partially obstructing various passageways.
 - 18 4. **Pressure Relief Valves (PRVs):** Safety devices designed to open at a
19 predetermined pressure to prevent an excess pressure build-up that could
20 jeopardize the pipeline's structural integrity.
 - 21 5. **Emergency Shutdown Systems (ESDs):** Systems designed to rapidly
22 shut down compressor station equipment and/or facilities under certain
23 conditions in the event of a detected leak or other hazardous situations that
24 will isolate sections of the pipeline to minimize risks.
 - 25 6. **Pressure Limiting Station (PLS):** Devices that regulate or limit the flow
26 of gas at a specific set point to achieve or maintain a certain pressure to
27 keep pipeline operations within the determined pressure limits.
 - 28 7. **Pig Launchers & Receivers:** Facilities used for the insertion and retrieval
29 of in-line inspection tools used to clean and inspect the pipeline.
 - 30 8. **Metering Stations:** Stations that measure the flow rate of hydrogen
31 through the pipeline and are utilized for operational control and billing
32 purposes.
 - 33 9. **Corrosion Protection Systems:** Includes cathodic protection and
34 protective coatings that are designed to prevent internal and external
35 corrosion.
 - 36 10. **Leak Detection Systems:** Technologies deployed along the pipeline to
37 detect and locate leaks based on pressure, acoustic signals, or chemical

1 sensors. These components are essential for the early detection of failures
2 or breaches in pipeline integrity.

3 **11. Control & Monitoring Systems:** Centralized systems that use field
4 technology, sensors and communication methods to monitor and control
5 the physical parameters of the pipeline.

6 Additionally, as indicated in the Design Study, the final design of a system and the
7 selection of the above components will take into account federal, state, and industry codes and
8 standards. The system will be designed to meet operational requirements, account for Angeles
9 Link system facility locations, and support construction, operations, and integrity management
10 objectives.

11 **IV. SOCALGAS SYSTEM DESIGN**

12 SoCalGas will design the Angeles Link system in accordance with best practices
13 common to the industry, including the safety and design codes and standards applicable to the
14 engineering, construction, and operation of a hydrogen gas transportation pipeline system.¹⁶
15 SoCalGas will incorporate appropriate safety features into the Angeles Link system design, such
16 as automated and remote-control valves. These enhanced valves detect operating abnormalities
17 and either automatically close or alert the gas control center to take action. SoCalGas will
18 evaluate the design of similar valve functionality safety features into the Angeles Link system
19 design. SoCalGas will also seek to evaluate and design an optical pipeline monitoring system
20 feature for Angeles Link, as appropriate. This type of system allows for advanced right-of-way
21 intrusion detection and monitoring to provide early warning of digging, drilling, boring, cutting,
22 or compacting, or if unplanned vehicle operations by third parties pose a threat to pipeline
23 integrity. The system also allows for continuous monitoring of ground movement and
24 temperature gradients associated with an unplanned release of gas from the pipeline.

25 **A. Project Team Activities**

26 To execute the Phase 2 Pre-FEED and FEED activities described in this testimony,
27 SoCalGas will assemble a project team that is comprised of personnel from Project Management,
28 Engineering, Cost and Schedule Controls, Cost Estimating, Construction Management,

¹⁶ These codes and standards are discussed in the Evaluation of Applicable Safety Requirements completed in Phase 1.

1 Operations, Permitting and Environmental Support, and Public Outreach. The project team will
2 be responsible for the management of the engineering design and project planning scope.
3 Complex infrastructure project development, such as the siting and design of a clean renewable
4 hydrogen pipeline system like Angeles Link, requires appropriate governance and management.
5 Accordingly, the activities described in my testimony will be overseen and evaluated
6 consistently by personnel from various SoCalGas organizations.

7 The project team will manage the engineering design and project planning scope of work
8 in collaboration with the programmatic scope of work described by Ms. Kitson. The project
9 team will receive inputs from the programmatic scope of work, such as the pipeline and
10 equipment material evaluation, which will support the development of requirements for
11 engineering design of the Angeles Link system. The project team will also provide information
12 such as scope, cost and schedule updates to facilitate programmatic cost monitoring and controls.
13 The following section discusses key project team functions, including both company labor and
14 non-labor resources.

15 SoCalGas intends to contract with a third-party engineering firm(s) to assist with Pre-
16 FEED and FEED activities. Throughout engineering development activities, the third-party
17 engineering firm and SoCalGas's project team (described below) will collaborate to execute
18 Phase 2 activities. Computer Aided Design (CAD) drawings, three-dimensional models,
19 narratives, studies, and reports will be generated by third-party engineering firms and reviewed
20 by the SoCalGas project team to address issues that might impact safety, construction,
21 operations, maintenance, environmental, and permitting requirements, taking into account
22 constructability and safety considerations.

23 **1. Project Management**

24 To enable the ramp up of project activities during Phase 2, SoCalGas will utilize internal
25 and external resources to perform project management functions. Internal and external project
26 managers will work closely with the engineering team and other stakeholders to develop the
27 necessary deliverables to support the completion of Pre-FEED and FEED. Project managers will
28 serve as the key points of contact for communicating work direction to other project
29 stakeholders, contract management, managing project scope, managing progress, and keeping
30 leadership apprised of progress during Phase 2.

1 Project management services such as document control, change control, and project
2 administration will be needed to support the management of documents created during Pre-
3 FEED and FEED. Documents will be administered through a computer document management
4 system for accurate project documentation and change management implementation.

5 **2. Engineering**

6 For Phase 2, SoCalGas and the selected engineering consultant firm(s) will coordinate to
7 complete engineering design of the Angeles Link system. SoCalGas will use both internal and
8 external resources to support the Pre-FEED and FEED engineering activities. SoCalGas's Gas
9 Engineering organization, in coordination with third-party engineers as needed, will provide
10 technical support for Pre-FEED and FEED activities such as developing design requirements and
11 performing QA/QC of the engineering design. This includes both project engineering
12 coordination and various engineering disciplines.

13 In addition to the FEED engineering consultant, additional third-party specialty
14 engineering firms may be retained, as needed, to support engineering activities, such as preparing
15 permit packages for any Phase 2 field activities (e.g., surveys or ground studies) and carrying out
16 geotechnical and environmental evaluations.

17 **3. Engineering Design Project Controls**

18 The project team will utilize project management resources to implement project
19 governance related to the execution of Pre-FEED and FEED activities. These resources will
20 support activities such as Project Delivery Model process assurance, regulatory program
21 management, cost controls, schedule management, and estimating. The implementation of
22 proper controls and management across the functional areas will help verify that each component
23 of Phase 2 activities is performed consistent with SoCalGas's processes.

24 **4. Cost and Schedule Controls**

25 The project cost and scheduling team will track and report on performance indicators
26 (e.g., variance reporting) and facilitate communication among the project team and key
27 SoCalGas stakeholders regarding cost and schedule. These cost and schedule controls will assist
28 the project team in identifying critical project activities along with changes compared to project
29 baseline plans. Both internal and external resources will be utilized for project cost and schedule
30 controls.

1 **5. Cost Estimating**

2 SoCalGas, in conjunction with input from third-party contractors, will develop cost
3 estimates during Phase 2. The estimate deliverables are typically comprised of an estimate basis,
4 estimate details, and a contingency recommendation that takes into account project risks.
5 Developing a cost estimate on a project of this scale is an iterative process. Proposed project
6 cost estimates will be produced at the end of Pre-FEED before FEED activities commence (Class
7 4 cost estimate) and at the end of the FEED study (Class 3 cost estimate). Additionally, at the
8 end of Pre-FEED activities, an updated estimate to complete FEED-stage activities will be
9 produced based upon the design development that has occurred. These updates will take into
10 account the more detailed information and scope refinement from the completed and forecasted
11 activities.

12 **6. Construction Management**

13 During Phase 2, internal and external construction management resources will work
14 collaboratively to perform preliminary scoping, constructability reviews, and support the
15 development of the project execution plan, schedule, and cost estimate. They will be integrated
16 into project development early in Phase 2 to provide input on constructability considerations,
17 identify potential risks to the construction schedule and costs, and assist with the identification of
18 construction impacts and factoring them into the cost estimate and future permitting efforts.

19 **7. Operations**

20 The operations teams that manage and operate SoCalGas’s existing pipeline system will
21 support Angeles Link system development by providing input on system operability. Operations
22 will be consulted for their input on aspects of engineering design such as pipeline routing,
23 facility siting, equipment selection, maintainability, and operability.

1 **8. Ministerial Permitting and Environmental Support**

2 Permitting and environmental support will be an important element of the Pre-FEED and
3 FEED process as considerable upfront planning is necessary. These activities will be supported
4 by two separate but coordinated teams: the Permitting team and the Environmental team.¹⁷

5 The Permitting team will support ministerial permitting necessary to conduct Phase 2
6 field work. These actions/permits may include street use permits, traffic control permits, or
7 related items for exploratory investigations (e.g., surveys and soil testing) and permits associated
8 with contractor-owned equipment. The Permitting team will help oversee and/or complete
9 permit application packages, coordinate with the engineering team, permitting authority,
10 landowners and contractors as applicable, facilitate site inspections by the permitting authority,
11 and other related activities.

12 The Environmental team will be utilized to manage any environmental activities
13 associated with the Phase 2 Angeles Link system design. The environmental team will
14 coordinate with third parties to conduct necessary surveys and environmental analyses, review
15 data, and perform QA/QC on third-party environmental work described above.

16 **9. Public Outreach**

17 SoCalGas’s public outreach organization conducts project-specific efforts to inform
18 impacted stakeholders including customers, community groups, and local permitting offices
19 about SoCalGas project-related activities taking place in their communities. These efforts have
20 been, and continue to be, an integral part of SoCalGas’s Project Delivery Model. SoCalGas
21 proposes that, during Phase 2 of Angeles Link, the public outreach team will work closely with
22 the project team to engage with local communities, including nearby residents, businesses, and
23 stakeholders, to communicate Phase 2 project-specific impacts. Costs included in the Pre-
24 FEED/FEED forecast presented below are limited to project public outreach efforts that would
25 be needed to support field activities for engineering development (e.g., survey, environmental
26 surveys). Stakeholder engagement costs are different and are discussed and included in the
27 forecast presented by Ms. Kitson.

¹⁷ The Permitting and Environmental teams will also engage outside consultants to support permitting and environmental activities, including but not limited to focused biological surveys, cultural resource surveys, and other related materials.

1 **B. Procurement**

2 In selecting contractors for both Pre-FEED and FEED (and the programmatic activities
3 discussed by Ms. Kitson), SoCalGas will endeavor to evaluate, select, and retain qualified
4 suppliers and contractors at reasonable rates. SoCalGas plans to utilize market competition (e.g.,
5 competitive bidding) to obtain services at market-based rates to the extent feasible.¹⁸ The
6 process for competitively bidding contracts involves soliciting bids from potential contractors
7 based on the scope, specifications, and terms and conditions of the proposed contract. While
8 pricing is a major consideration in the selection process, other factors such as safety, supplier
9 performance, supplier experience, key personnel, lifecycle cost analyses, diverse business
10 enterprise (DBE) participation, and history, among others, are also typically considered for
11 award recommendation and contractor selection.^{19,20}

12 In addition to individual bidding events, as appropriate, SoCalGas may execute
13 agreements by leveraging terms and conditions and rates from existing agreements. This avoids
14 administrative costs, uses previously negotiated rates, and allows SoCalGas to commence work
15 on an expedited basis. This work typically commences through releases issued pursuant to a
16 Master Service Agreement (MSA). Releases from an MSA are used to authorize services and
17 memorialize any commercial and technical terms for a specific scope of work, compensation
18 schedule, and delivery/performance schedule in accordance with the terms and conditions of the
19 MSA. For tracking purposes, these MSAs and releases are considered single-sourced because a
20 separate individual bidding does not occur. Although tracked as single-source, releases from
21 MSAs that were implemented using market-based rates further promote cost reduction by
22 avoiding logistical costs associated with separate bidding events. In these instances, SoCalGas
23 capitalizes on previous efforts to competitively bid, vet, and negotiate contracts, thus promoting

¹⁸ Utilizing non-labor services with unique skills and experience associated with hydrogen pipelines may require sole-sourcing. Sole-sourcing best practices will be utilized as needed.

¹⁹ Procuring services from diverse businesses is a CPUC goal (General Order (GO) 156 at 16, *available at: <https://www.cpuc.ca.gov/-/media/cpuc-website/divisions/news-and-outreach/documents/bco/go-156-d22-04-035.pdf>*) that SoCalGas has consistently exceeded annually for the past 31 years. In 2023, SoCalGas reported purchasing 44% of all goods and services from minority, women, service-disabled veteran, and LGBT-owned businesses, amounting to over \$1 billion to 618 diverse businesses, of which almost 87% are based in California.

²⁰ Development of a procurement plan in Phase 2 will consider domestic sourcing of equipment, materials, and labor.

1 market-based rates, leveraging earlier efforts to competitively source vendors and contractors,
 2 and achieving cost-effective and expeditious project commencement.

3 **C. Schedule**

4 As described by Mr. Navin, SoCalGas’s efforts to meet ARCHES’ timeline for operation
 5 of the California Hydrogen Hub are dependent on swift commencement of Phase 2 when
 6 Commission approval is granted.²¹ Therefore, as stated above, SoCalGas intends to begin
 7 certain contracting activities in 2025 in support of the Phase 2 schedule. These activities, which
 8 are anticipated to take approximately one year, will enable SoCalGas to then transition to Phase
 9 2 beginning in 2026. SoCalGas estimates that, in total, Phase 2 activities will span
 10 approximately 30 months following a decision in this proceeding, estimated to start in January
 11 2026 (see Figure 3 below). The schedule is based on a number of preliminary assumptions, such
 12 as assumed production rates (how quickly work can be performed), number of engineering teams
 13 supporting the project, schedule predecessors (i.e., items required to be performed before another
 14 item can start), and internal reviews.

Angeles Link	2025				2026				2027				2028			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Contracting Activities	█															
Contracting Activities	█															
Phase 2 - Pre-FEED/FEED Schedule					█				█				█			
Pre-FEED					█				█							
Route & Facilities Planning and Optimization					█				█							
Compressor Station Study					█				█							
FEED									█				█			
Route & Facilities Design									█				█			
Compressor Station Design									█				█			

15 **Figure 3 – Angeles Link Phase 2 Schedule**

16 The schedule is anticipated to be iterative in nature and will be adjusted during the course
 17 of Pre-FEED and FEED as new information is obtained, such as when the preferred system route
 18 is selected and Pre-FEED activities are completed.

²¹ Testimony of Neil Navin at Section IV.

1 **V. COST FORECAST**

2 As shown in Table BW-1 below, the Phase 2 costs I am sponsoring total approximately
3 \$216 million.²² These costs primarily comprise labor and non-labor costs necessary to support
4 identification of a preferred system route, perform engineering design, environmental
5 assessments, and project management activities associated with progressing the Angeles Link
6 clean renewable hydrogen pipeline system through FEED. However, the costs are also inclusive
7 of the aforementioned contracting activities, to be commenced in 2025, that are critical to
8 enabling SoCalGas to quickly transition to Phase 2 with its selected vendors ready when the
9 Commission issues its final decision. These contracting activities are necessary for SoCalGas to
10 meet its schedule objectives, and furthermore provide cost savings benefits for ratepayers. By
11 initiating contracting activities in 2025, SoCalGas can mitigate the additive impacts of escalation
12 costs that would otherwise be incurred if these activities were deferred to later years. SoCalGas
13 estimates that the associated benefit to ratepayers as a result of initiating activities in 2025 is
14 approximately \$5 million.

15 **Table 1**
16 **Phase 2 Engineering Design Cost Forecast (in millions)**

	2025	2026	2027	2028	Total
Total Direct O&M Costs	4.0	56.0	86.1	48.4	194.4
Direct Labor	2.2	5.3	6.8	3.3	17.6
Direct Non-Labor	1.7	50.7	79.2	45.2	176.8
Total Fully Loaded O&M Costs	5.7	61.5	94.9	53.4	215.5

17 **A. Phase 2 Cost Forecasting Methodology**

18 SoCalGas developed a cost forecast to complete Phase 2 engineering design for the
19 Angeles Link system using AACEi principles and common practices associated with projects in
20 development. The following describes the process that was used to develop the cost forecast;
21 additional detail is provided in the supplemental workpaper supporting my testimony.

22 The SoCalGas estimating team developed the cost forecast based on the project's
23 assumed scope from the Phase 1 feasibility studies, including routing information from the

²² The costs reflected herein are all Operating and Maintenance (O&M) costs, which include direct costs, adjusted for applicable overhead loaders, escalation, and other necessary costs. Additional discussion of SoCalGas's proposed cost treatment is provided in the Testimony of Nasim Ahmed and Michael W. Foster.

1 Preliminary Routing and Configuration Analysis. The forecast assumes a route length of 481
2 miles, which correlates to a potential directional route option (Route D) identified in the Phase 1
3 Preliminary Routing and Configuration Analysis. This was the longest route considered in the
4 analysis; it was selected to account for alignment variations that will be evaluated during FEED.
5 The forecast also assumes that two 50,000 horsepower compressor stations will be required.
6 These assumptions anchored the estimating scope so the Phase 2 cost forecast could be
7 developed.

8 In developing the Phase 2 cost forecast in Table BW-1, SoCalGas utilized ACEI
9 principles to develop an activity-based, bottom-up approach to identify direct costs for the
10 completion of Pre-FEED and FEED activities. This approach derives the total cost “from the
11 summation of detailed estimates for all the individual constituent components of the project.
12 This method aims at constructing the estimate of a system from the knowledge accumulated
13 about the small components and their interactions.”²³ This method results in a structured
14 estimate that can be tracked and managed.

15 Specifically, project engineering and design, project management, environmental, and
16 other cost categories were estimated through various methodologies and experience from
17 previous projects. A deliverable list for pipeline and compressor station components was
18 compiled and labor hours were estimated to complete each deliverable. Project packages,
19 deliverables, levels of effort, and staff hours were based on historical experience and expert
20 judgment. Critical assumptions such as engineering design drawing sheet-count per mile,
21 number of valve stations, alternative installations, and level of effort per drawing sheet for all
22 pipeline segments were also derived in this manner.

23 Project cost estimates will evolve with the advancement of project definition. As with all
24 project estimates, the forecast for Phase 2 Pre-FEED and FEED work includes assumptions,
25 constraints, uncertainty, and perceptions of risk.²⁴ The Angeles Link system is early in the
26 project development lifecycle as identified above, with project definition maturity level
27 estimated at 1-2%. At this early time in the project development lifecycle, there is typically a

²³ PMI, *Practice Standard for Project Estimating – Second Edition* (January 2020) at 50.

²⁴ *Id.* at 21.

1 reduced estimate confidence and accuracy, which necessitates a larger confidence range. As the
2 project definition advances, a smaller confidence range is typically utilized.

3 SoCalGas also conducted a risk assessment for Phase 2 engineering design and project
4 management activities in order to perform a Monte Carlo simulation analysis to generate a
5 contingency amount to be applied to the base forecast. The risk assessment took into
6 consideration the current maturity of project definition. According to AACEi, contingency is
7 “an amount added to an estimate to allow for items, conditions, or events for which the state,
8 occurrence, or effect is uncertain and that experience shows will likely result, in aggregate, in
9 additional costs.”²⁵ Contingency is “typically estimated using statistical analysis or judgment
10 based on past asset or project experience.”²⁶ Using the AACEi contingency methodology,
11 SoCalGas identified an average contingency percentage of 24% that was included in the Phase 2
12 Engineering Design Cost Forecast presented herein. This percentage is within the range of
13 expected contingency for projects that are in a preliminary stage of development and reflects
14 SoCalGas’s careful consideration of risks through the aforementioned AACEi methodology that
15 is widely accepted.²⁷ Contingency is expected to be expended during the execution of Phase 2;
16 however, it is not a provision to cover major changes in scope or execution.

17 **B. Cost Controls**

18 SoCalGas will implement project controls to execute Phase 2 of Angeles Link on
19 schedule and at reasonable cost, while producing quality deliverables and meeting applicable
20 engineering standards and regulatory requirements. The Pre-FEED and FEED methodologies
21 and the stage-gate approach SoCalGas will employ during Phase 2 are industry standard
22 processes for large infrastructure projects. Further, cost controls are an important part of
23 SoCalGas’s Project Delivery Model and have been exercised effectively on other recent
24 programs.²⁸ A dedicated Project Controls team will be responsible for performing cost controls

²⁵ AACEi, *Recommended Practice 10S-90: Cost Engineering Terminology* (July 24, 2024) at 31, available at: <https://web.aacei.org/docs/default-source/rps/10s-90.pdf>.

²⁶ *Id.*

²⁷ The Commission has ruled in SoCalGas’s favor regarding the estimation of contingency in this manner in both D.19-03-025 and D.19-09-051.

²⁸ See PSEP Decisions D.16-12-063, D.19-02-004, D.19-03-025, and D.20-08-034; approval for recovery of Storage Integrity Management Program Balancing Account (SIMPBA) costs in

1 for Angeles Link. The Project Controls team, in coordination with SoCalGas's Project
2 Management team discussed above, will implement a cost management plan for Phase 2 to:
3 estimate the planned resources; convert the estimates to a time-phased budget; monitor
4 expenditures and cash flow as the work proceeds; identify incorrect or unapproved charges;
5 manage changes to the baseline as they occur; take corrective actions; continuously forecast the
6 final cost of the project; and report the status of project costs to key stakeholders and leadership.

7 Effective cost management is a necessary endeavor that promotes confidence in
8 completing the defined scope of work within the approved budget, mitigating possible risks, and
9 proactively controlling cost variances. To accomplish these objectives in Phase 2, SoCalGas will
10 utilize cost control concepts that are widely practiced by infrastructure project practitioners such
11 as Earned Value Management and the development of an Estimate at Completion (EAC)
12 forecasted budget. Consistent with best practices for project management, actual and forecasted
13 costs will be updated and tracked. Costs will be tracked through the creation of internal order
14 numbers which will then be used to record expenditures. Cost tracking reports will be utilized to
15 monitor incurred expenditures against forecast. Forecast changes will be reported and reviewed
16 with the Project Team periodically to determine the required action(s).

17 **VI. CONCLUSION**

18 This concludes my prepared direct testimony.

Resolution G-3544 at 4-5; approval for recovery of Transmission Integrity Management Program
Balancing Account costs in Resolution G-3600 at 5-9.

1 **VII. CHAPTER 4 GLOSSARY²⁹**

- 2 ○ Association for the Advancement of Cost Engineering International (AACEi) –
3 An industry leading organization in the field of cost estimating. AACEi guidelines
4 and standards are used by SoCalGas to develop cost estimates for all major capital
5 projects, inclusive of pipelines and complex facilities such as compressor stations.
- 6 ○ Baseline – The approved version of a work product, used as a basis for
7 comparison to actual results.
- 8 ○ Budget – The approved estimate for the project or any work breakdown structure
9 (WBS) component or any schedule activity.
- 10 ○ Change – A modification to any formally controlled deliverable, project
11 management plan component or project document.
- 12 ○ Change Control – A process whereby modifications to documents, deliverables,
13 or baselines associated with the project are identified, documented, approved or
14 rejected.
- 15 ○ Class 3 Estimate – Generally produced at the conclusion of FEED when a 30%
16 design package is available. Typically, engineering is 10 to 40% complete;
17 therefore, a higher level of accuracy is anticipated and may fall within the range
18 of -20% to +30%. According to AACE, Class 3 estimates are “generally prepared
19 to form the basis for budget authorization, appropriation, and/or funding. As such,
20 they typically form the initial control estimate against which all actual costs and
21 resources will be monitored.”³⁰
- 22 ○ Class 4 Estimate – Generally produced at the conclusion of Pre-FEED. Typically,
23 engineering is 1 to 15% complete; therefore, accuracy is limited and may fall
24 within the range of -30% to +50%. These estimates are often used for project
25 screening, concept evaluation, and preliminary budget approval.
- 26 ○ Complexity – A characteristic of a program or project or its environment that is
27 difficult to manage due to human behavior, system behavior, and ambiguity.

²⁹ This section references the *PMBOK Guide: A Guide to the Project Management Body of Knowledge*.

³⁰ AACEi RP 97R-18 at 10.

- 1 ○ Contingency – An event or occurrence that could affect the execution of the
2 project, which may be accounted for with a reserve.
- 3 ○ Control – The process of comparing actual performance with planned
4 performance, analyzing variances, assessing trends to effect process
5 improvements, evaluating possible alternatives, and recommending appropriate
6 corrective action as needed.
- 7 ○ Deliverable – Any unique and verifiable product, result, or capability to perform a
8 service that is required to be produced to complete a process, phase, or project.
- 9 ○ Earned Value – The measure of work performed expressed in terms of the budget
10 authorized for that work.
- 11 ○ Estimate – A quantitative assessment of the likely amount or outcome of a
12 variable, such as project costs, resources, effort or durations.
- 13 ○ Forecast – An estimate or prediction of conditions and events in the project’s
14 future based on information and knowledge available at the time of the forecast.
- 15 ○ Governance – The framework for directing and enabling an organization through
16 its established policies, practices and other relevant documentation.
- 17 ○ Estimate at Completion (EAC) – The expected total cost of completing all work
18 expressed as the sum of the actual cost to date and the estimate to complete.
- 19 ○ FEED (Front-End Engineering Design) - The process through which the
20 engineering design of the system route identified during Pre-FEED is advanced to
21 30% design level, which would support a Class 3 estimate.
- 22 ○ Incremental Approach – An adaptive development approach in which the
23 deliverable is produced successively, adding functionality until the deliverable
24 contains the necessary and sufficient capability to be considered complete.
- 25 ○ Issue – A current condition or situation that may have an impact on the project
26 objectives.
- 27 ○ Iterative Approach – A development approach that focuses on an initial,
28 simplified implementation then progressively elaborates adding to the feature set
29 until the final deliverable is complete.

- 1 ○ Lessons Learned – The knowledge gained during a project, which shows how
2 project events were addressed or should be addressed in the future, for the
3 purpose of improving future performance.
- 4 ○ Monitor – Collect project performance data, produce performance measures, and
5 report and disseminate performance information.
- 6 ○ Monte Carlo Simulation – A method of identifying the potential impacts of risk
7 and uncertainty using multiple iterations of a computer model to develop a
8 probability distribution of a range of outcomes that could result from a decision or
9 course of action.
- 10 ○ Plan – A proposed means of accomplishing something.
- 11 ○ Pre-FEED (Pre-Front-End Engineering Design) - References to Pre-FEED
12 activities in Phase 2 refer to those Phase 2 activities to advance the work done
13 during Phase 1 and to select a preferred system route and further refine pipeline
14 system design and requirements to develop the information needed to complete a
15 FEED study for the preferred system route.
- 16 ○ Project – A temporary endeavor undertaken to create a unique product, service or
17 result.
- 18 ○ Project Governance – The framework, functions, and processes that guide project
19 management activities in order to create a unique product, service or result to
20 meet organizational, strategic, and operational goals.
- 21 ○ Project Lifecycle – The series of phases that a project passes through from its start
22 to its completion.
- 23 ○ Project Execution Plan – The document that describes how the project will be
24 executed, monitored and controlled, and closed.
- 25 ○ Project Management Team – The members of the project team who are directly
26 involved in project management activities.
- 27 ○ Project Manager – The person assigned by the performing organization to lead the
28 team that is responsible for achieving the project objectives.
- 29 ○ Project Schedule – An output of a schedule model that presents linked activities
30 with planned dates, durations, milestones and resources.

- 1 ○ Project Scope – The work performed to deliver a product, service, or result with
2 the specified features and functions.
- 3 ○ Project Team – A set of individuals performing the work of the project to achieve
4 its objectives.
- 5 ○ Proponent’s Environmental Assessment (PEA) – is an environmental assessment
6 that must be included with any CPUC Public Convenience and Necessity (CPCN)
7 or Permit to Construct (PTC) application for authority to undertake a project that
8 is not statutorily or categorically exempt from the requirements of the California
9 Environmental Quality Act (CEQA). CPUC Rules of Practice and Procedure,
10 available at: [https://www.cpuc.ca.gov/-/media/cpuc-](https://www.cpuc.ca.gov/-/media/cpuc-website/divisions/administrative-law-judge-division/documents/rules-of-practice-and-procedure-may-2021.pdf)
11 [website/divisions/administrative-law-judge-division/documents/rules-of-practice-](https://www.cpuc.ca.gov/-/media/cpuc-website/divisions/administrative-law-judge-division/documents/rules-of-practice-and-procedure-may-2021.pdf)
12 [and-procedure-may-2021.pdf](https://www.cpuc.ca.gov/-/media/cpuc-website/divisions/administrative-law-judge-division/documents/rules-of-practice-and-procedure-may-2021.pdf).
- 13 ○ Quality Management Plan – A component of the project or program management
14 plan that describes how applicable policies, procedures, and guidelines will be
15 implemented to achieve the quality objectives.
- 16 ○ Report – A formal record or summary of information.
- 17 ○ Requirement – A condition of capability that is necessary to be present in a
18 product, service, or result to satisfy a business need.
- 19 ○ Risk Register – A repository in which outputs of risk management processes are
20 recorded.
- 21 ○ Risk Review – The process of analyzing the status of existing risks and
22 identifying new risks.
- 23 ○ Specification – A precise statement of the needs to be satisfied and the essential
24 characteristics that are required.
- 25 ○ Stakeholder Engagement Plan – A component of the project execution plan that
26 identifies the strategies and actions required to promote productive involvement
27 of stakeholders in project or program decision making and execution.
- 28 ○ Verification – The evaluation of whether or not a product, service, or result
29 complies with a regulation, requirement, specification, or imposed condition.

1
2
3
4
5

- Work Breakdown Structure (WBS) – A hierarchical decomposition of the total scope of work to be carried out by the project team to accomplish the project objectives and create the required deliverables.
- Work Package – The work defined at the lowest level of the work breakdown structure for which cost and duration are estimated and managed.

1 **VIII. QUALIFICATIONS**

2 My name is Brian J. Walker. I presently hold the position of Director of Project
3 Management for SoCalGas. I hold a Bachelor of Science degree in Mechanical Engineering and
4 a Master's degree in Business Administration from California Polytechnic State University,
5 Pomona.

6 I have a broad background in engineering and natural gas pipeline operations with over
7 17 years of experience with SoCalGas. I have held a number of technical and managerial
8 positions with increasing responsibility in the Gas Engineering, Gas Transmission, Gas Control
9 & System Planning, and Construction Departments. In these positions, I have been responsible
10 for engineering, field operations, gas system control operations, project management, and
11 construction. I have held my current position as the Director of Project Management since
12 September 2022.

13 I have not previously testified before the Commission.